



ADDENDUM No. 1

Request for Proposals CWA-2016-01

INSTALLATION OF ON-SITE SEWAGE FACILITIES IN THE ATTOYAC BAYOU WATERSHED

Addendum Issued 1/29/2016

CLARIFICATIONS AND MODIFICATIONS TO THE RFP

For the purposes of calculating the Base Bid for aerobic On-Site Sewage Facilities to be installed for this Project, and to assure that Installers are bidding on the same quantities and types of materials, please use the following assumptions:

- 1.) PVC Sewer Pipe: The Base Bid should include 50' of 4" SDR 26 PVC or 4" Schedule 40 PVC pipe to connect the residence to the treatment system. Any pipe in excess of 50' in length may be billed as an Add-On cost on a linear foot basis, with the price to include both materials and labor.
- 2.) Sprinkler Pipe: The Base Bid should include 200' of ¾" purple Schedule 40 PVC pipe for the irrigation of effluent from the treatment system. Any pipe in excess of 200' in length may be billed as an Add-On cost on a linear foot basis, with the price to include both materials and labor.
- 3.) Electrical Conduit: The Base Bid should include 60' of conduit and wiring to connect residential electrical service to the treatment system. Any conduit and wiring in excess of 60' in length may be billed as an Add-On cost on a linear foot basis, with the price to include both materials and labor.

This Addendum is posted on ANRA's website at the following address:

http://www.anra.org/about/public_information/news/OSSF_bid_invitation_2016-01.html

**PREPARED IN COOPERATION WITH THE
TEXAS COMMISSION ON ENVIRONMENTAL QUALITY AND
U.S. ENVIRONMENTAL PROTECTION AGENCY**

This project has been funded wholly or in part by the United States Environmental Protection Agency under assistance agreement to Texas Commission on Environmental Quality. The contents of this document do not necessarily reflect the views and policies of the Environmental Protection Agency, nor does the EPA endorse trade names or recommend the use of commercial products mentioned in this document.